

Stormwater Pollution Prevention Plan

For:

Overton Airport



**Clark County Department of Aviation
Environmental, Safety, and Risk Management Section**

**SWPPP Preparation Date:
December 2009**

TABLE OF CONTENTS

1.0 Introduction	1
1.1 Purpose	1
1.2 Regulatory Background	1
2.0 Facility Information	1
2.1 Facility Description	1
2.2 Facility Contact Information	2
2.3 Facility Characteristics	2
3.0 Site Evaluation and Assessment	2
3.1 Potential Source Information	2
3.1.1 Aircraft Fueling	3
3.1.2 Aircraft Maintenance	3
3.1.3 Aircraft Washing	3
3.1.4 Chemical and Petroleum Product Storage	4
3.1.5 Facility Maintenance	4
3.1.6 Pesticide and Herbicide Use	4
3.1.7 Refuse Containers	4
3.2 Potential Non-Stormwater Pollutants	4
4.0 Best Management Practices	5
4.1 Aircraft Fueling	5
4.2 Aircraft Maintenance	5
5.0 Inspections and Audits	6
5.1 Quarterly Facility Inspections	6
5.2 Annual Facility Audits	6
5.3 Enforcement	7
6.0 Recordkeeping	7
7.0 Certification	7

APPENDICES

Appendix A	General Stormwater Permit, Notice of Intent, and NDEP Approval letter
Appendix B	Site Maps
Appendix C	Drainage Maps
Appendix D	SWPPP Amendment Log
Appendix E	Inspection Records and Checklists
Appendix F	Non-Stormwater Discharge Assessment and Certification Sheet
Appendix G	Annual Tenant Questionnaires
Appendix H	Annual SWPPP Compliance Report

1.0 Introduction

1.1 Purpose

The purpose of the Overton Airport Stormwater Pollution Prevention Plan is to ensure that the facility remains in compliance with the requirements of the National Pollutant Discharge Elimination System (NPDES) program administered by the Nevada Division of Environmental Protection and the United States Environmental Protection Agency. This document is intended to be utilized by the Clark County Department of Aviation (DOA) and tenants of the DOA to aid in the proper management of stormwater discharges at DOA facilities. To accomplish this, the Stormwater Pollution Prevention Plan identifies the existing and potential sources of contamination and the best management practices to be utilized to prevent impacts from these sources on Overton Airport stormwater discharges. This program shall be revised if there are changes in design, components, or if deemed necessary due to deficiencies observed by the DOA personnel or by regulatory agencies. This document shall be maintained on-site by the DOA Environmental, Safety, & Risk Management section and be made available upon request.

1.2 Regulatory Background

Polluted stormwater runoff is a leading cause of impairment to nearly 40 percent of surveyed U.S. water bodies which do not meet water quality standards. Over land or via storm sewer systems, polluted runoff is discharged, often untreated, directly into local water bodies. When left uncontrolled, this water pollution can result in the destruction of fish, wildlife, and aquatic life habitats; a loss in aesthetic value; and threats to public health due to contaminated food, drinking water supplies, and recreational waterways.

Mandated by Congress under the Clean Water Act, the NPDES Stormwater Program is a comprehensive two-phased national program for addressing the non-agricultural sources of stormwater discharges which adversely affect the quality of our nation's waters. The program uses the NPDES permitting mechanism to require the implementation of controls designed to prevent harmful pollutants from being washed by stormwater runoff into local water bodies.

The Nevada Division of Environmental Protection (NDEP) Stormwater General Permit NVR050000 requires facilities to submit a Notice of Intent in order to obtain coverage under an NPDES stormwater permit and implement stormwater pollution prevention plans (SWPPPs) using best management practices that effectively reduce or prevent the discharge of pollutants into receiving waters. In order to obtain authorization for stormwater discharges under the General Permit, NDEP requires entities to submit a Notice of Intent. Appendix A includes the NDEP Stormwater General Permit, the Notice of Intent, and the approval letter for Overton Airport. The permit shows DOA as the permittee and although tenants are not listed on the permit, all tenants are considered as co-permittees. This SWPPP has been prepared in accordance with the requirements of the Nevada General Stormwater Permit.

2.0 Facility Information

2.1 Facility Description

Overton Airport, previously known as Perkin's Field, is physically located at 1110 Airport Road in Overton, Nevada. However, all correspondence related to this program should be addressed to the DOA Environmental Coordinator, P.O. Box 11005, Las Vegas, Nevada 89111. The facility is owned by Clark County and operated by the DOA. The facility consists of an office trailer, tenant hangars, and the associated ramps and runways.

The DOA Environmental, Safety, and Risk Management Section is responsible for ensuring this program is implemented throughout the facility. A site map indicating the general location of the Overton Airport and the locations of the above structures is included as Appendix B.

2.2 Facility Contact Information

Permittee:	Site Supervisor:
Clark County Department of Aviation	Clark County Department of Aviation
Environmental, Safety, & Risk Management Section	Attn: Environmental, Safety, & Risk Management
Attn: Environmental Coordinator	Administrator
P.O. Box 11005	P.O. Box 11005
Las Vegas, NV 89111	Las Vegas, NV 89111
(702) 261-5525	(702) 261-5525

SWPPP Contacts:	Emergency 24-Hour Contact:
Clark County Department of Aviation	Clark County Department of Aviation
Environmental, Safety, & Risk Management Section	Control Center
Attn: Environmental Coordinator	(702) 261-5125
P.O. Box 11005	
Las Vegas, NV 89111	
(702) 261-5525	

2.3 Facility Characteristics

Overton Airport encompasses approximately 273.40-acres of which 24.70-acres consist of paved surface, 0.07-acres are structures, and 0.0-acres is landscaping. The annual precipitation in Las Vegas was 5.87-inches based on data from the National Weather Service for the years 2000 through 2004. The National Weather Service data also indicates that January to March is when most of this precipitation can be expected. The drainage at Overton Airport generally flows from the north to the south and discharges into the Muddy River, which discharges into Lake Mead. A site map showing the existing drainage patterns and systems is attached as Appendix C.

3.0 Site Evaluation and Assessment

3.1 Potential Source Information

The potential pollutant discharge activities conducted by the tenants and DOA personnel were identified and were evaluated for the potential to degrade stormwater quality. The activities, potential pollutant source, and the potential pollutants associated with these activities are provided in Table 1.

Table 1: Activities

Activity	Potential Pollutant Source	Potential Pollutant
Aircraft fueling	Fueling, spills/leaks	Fuels
Aircraft maintenance	Spills/leaks, hazardous and non-hazardous wastes, parts cleaning, waste oils and fluids, and oily rags	Solvents, oil, heavy metals, acid/alkaline wastes
Aircraft washing	Washing and rinsing	Petroleum products, total suspended solids, turbidity
Chemical and petroleum product storage	Spills/leaks, improper storage	Petroleum products, solvents, oils, grease, organics, acids
Facility Maintenance	Oils and grease, condensate, cleaners	Oils and grease, turbidity, solvents
Pesticide and herbicide use	Spills/leaks	Pesticide and herbicide residues
Refuse containers	Improper disposal, overfilling	Total suspended solids, turbidity, grease, organics

3.1.1 Aircraft Fueling

Aircraft fueling activities only occur on paved surfaces. All aircraft fueling is performed via the self-service island, which is owned and maintained by DOA. Spills and leaks can potentially occur during these activities. All spills are reported to the North Las Vegas Airport Customer Service Desk and promptly cleaned up by the responsible party. The DOA maintains a spill response cart placed near the self service island to aid in clean up activities. Spills occurring from fueling activities are of concern due to the potential to be a significant contributor of pollutants into the stormwater system.

3.1.2 Aircraft Maintenance

Tenants at Overton Airport conduct minor and routine maintenance of aircraft and associated equipment. Small spills and leaks are not uncommon during maintenance activities. Therefore, tenants are required to take precautions to prevent any release from entering the stormwater system and have spill clean up materials readily available during all maintenance activities. All spills are reported to the North Las Vegas Airport Customer Service Desk and promptly cleaned up by the responsible party. Spills occurring from maintenance activities are of concern due to the potential to be a significant contributor of pollutants into the stormwater system.

3.1.3 Aircraft Washing

Aircraft wet-washing activities are not allowed to occur at Overton Airport unless the wastewater from these activities is contained, properly stored, and subsequently properly disposed of. As all wastewater generated

during this activity is required to be collected, there should be no contribution of pollutants into the stormwater system.

3.1.4 Chemical and Petroleum Product Storage

Chemicals and petroleum products are stored in various locations throughout the facility and are owned by tenants and by the DOA. Depending on the area, these materials may be located in indoor storage areas and/or outdoor storage areas. Chemicals and petroleum products must be properly stored and labeled. This includes storing chemicals on spill pallets and in flammable materials lockers, where appropriate. All containers must remain in good condition and must be closed when not in use. Spill kits are required in all chemical and petroleum product storage locations. Spills have not occurred frequently in product storage areas. Therefore, spills occurring from chemical and petroleum product storage areas are of minor concern with regards to their potential to be a contributor of pollutants into the stormwater system.

3.1.5 Facility Maintenance

Facility Maintenance at Overton Airport includes repairs to and preventative maintenance activities on the buildings, roadways, ramps, systems, and equipment. DOA personnel, except in the privately owned hangars, conduct all of the facility repair or maintenance activities. Materials associated with these activities are stored primarily indoors or at an off-site location. All materials located on-site are required to be properly stored and labeled. All containers must remain in good condition and must be closed when not in use. All DOA employees and tenants are required to implement good housekeeping practices to reduce the possibility of impacts from materials on the ground surface. All spills are reported to the North Las Vegas Airport Customer Service Desk and promptly cleaned up by the responsible party. Spills have not occurred frequently in the maintenance materials storage areas. In addition, releases of these materials into the environment is unlikely as they are stored indoors. Therefore, spills occurring from these areas are of minor concern.

3.1.6 Pesticide and Herbicide Use

Minimal amounts of pesticides and herbicides are applied per the manufacturer's instructions by DOA personnel to select areas at Overton Airport. These materials are stored at an off-site location and therefore are not considered a significant contributor of pollutants into the stormwater system.

3.1.7 Refuse Containers

Dumpsters are provided and maintained by DOA for tenant use. These dumpsters have regularly scheduled pick-ups. Dumpsters are used for the disposal of common refuse. These dumpsters have minimal potential to contribute pollutants into the stormwater system.

3.2 Potential Non-Stormwater Pollutants

A non-stormwater discharge is a subtle and overt illicit connection into the stormwater system. A subtle illicit connection occurs when non-stormwater follows an unobstructed pathway into the stormwater system. The NDEP Stormwater General Permit authorizes only specific non-stormwater discharges to occur. Identified authorized non-stormwater discharges at Overton Airport include fire hydrant flushing, potable waterline flushing, roof drains, and air conditioning condensate. The occurrence of authorized non-stormwater discharges will be minimal. Any other non-stormwater discharges will be corrected upon discovery.

4.0 Best Management Practices

A Best Management Practice (BMP) is any schedule of activity, prohibitions of practices, maintenance procedures, and other management practices that eliminate, prevent, or reduce the potential to discharge pollutants into the stormwater system. BMPs may also include treatment requirements, operating procedures, and practices to control runoff, spillage or leaks, sludge and waste disposal, or drainage from raw material storage. BMPs are designed to ensure compliance with the stormwater permit and shall be revised if there are changes in the design, components, or processes on the facility, if inspections or compliance evaluations identify deficiencies, if deemed necessary by regulatory agencies, or whenever there is an unauthorized discharge.

4.1 Aircraft Fueling

BMPs implemented at Overton Airport to reduce the potential for pollutants to enter the stormwater system from aircraft fueling activities include:

- Check visible portions of the fueling system regularly for leaks.
- Verify all connections are secure before commencing fueling operations.
- Repair any leaks promptly.
- Hosing down or sweeping of spill areas into the stormwater system is prohibited.
- Maintain appropriate amounts of spill cleanup materials, enough material for at least a 100-gallon spill.
- Cleanup spills using rags or absorbent materials. Remove the materials promptly and properly dispose of cleanup materials.
- Ensure employees are trained in proper handling techniques, spill containment and cleanup measures, spill reporting requirements, and fueling procedures.

4.2 Aircraft Maintenance

BMPs implemented at Overton Airport to reduce the potential for pollutants to enter the stormwater system from aircraft maintenance activities include:

- Perform maintenance in appropriate locations.
- Keep all containers closed when not in use.
- Keep accurate maintenance logs.
- Utilize non-toxic chemicals when possible.
- Minimize the use of solvents or use water-based solvents.
- Recycle used oils when possible.
- Painting, other than minor brush on touch-ups, is prohibited.
- Pouring of materials into the storm drain system is prohibited.
- Ensure containers storing used fluids are properly maintained and labeled.
- Utilize drip pans or other containment devices for leaks until leak can be repaired.
- Promptly transfer used fluids from drip pans or other devices into proper containers.
- Drain oil-filters in an enclosed container for a minimum of 24-hours prior to disposal.
- Repair any leaks promptly.
- Maintain appropriate amounts of spill cleanup materials.
- Storage of batteries on the ground surface is prohibited.
- Recycle used batteries when possible.

- Keep equipment clean to avoid build-up of oils and greases.
- Store and label all containers properly.
- Cleanup spills using rags or absorbent materials. Remove the materials promptly and properly dispose of cleanup materials.
- Ensure employees are trained in proper spill containment, cleanup measures, and spill reporting requirements.

In addition to the above measures, the DOA as a supplementary BMP will conduct quarterly inspections of tenant lease areas to ensure compliance.

5.0 Inspections and Audits

DOA Environmental, Safety, and Risk Management (ES&RM) personnel will conduct quarterly inspections and audits of the facility in addition to any inspections or audits conducted by tenants at the facility. Should any deficiencies be identified during these inspections or audits, revisions or additions to this SWPPP will be made within 60-days of discovery. Any alterations made to this program will be documented and attached to a summary of the findings of the associated inspection or audit that initiated the changes. A copy of the SWPPP amendment log is attached as Appendix D. All records of inspections and audits will be maintained by ES&RM personnel and included with the SWPPP.

5.1 Quarterly Facility Inspections

DOA ES&RM personnel will conduct quarterly inspections of the facility. These will be conducted to determine if good housekeeping measures, spill prevention and response measures, maintenance programs, and other BMPs are being implemented and remain effective. These inspections will be documented through the use of a checklist. Completed inspection checklists will be maintained with the SWPPP. A copy of a blank checklist and subsequent completed checklists are attached as Appendix E.

Quarterly visual inspections of the stormwater system and discharge points will be conducted. If stormwater is present at the time of inspection, the condition of the water shall be documented. These conditions include the clarity and color; if suspended, floating, or settled solids are observed; if foam, oil sheen, or odors are present; and any other indicator of stormwater pollution. Any non-stormwater discharges observed shall be corrected immediately unless it is a permitted discharge. A non-stormwater discharge assessment and certification worksheet, as required by the Stormwater General Permit, must be completed for each quarterly inspection and maintained with the SWPPP. A blank copy of this worksheet and subsequent completed worksheets are attached as Appendix F.

5.2 Annual Facility Audits

DOA ES&RM personnel will conduct a comprehensive facility compliance audit annually. This audit will be conducted to determine if the SWPPP program is effective and if additional potential sources are present. Areas that will be audited will include, but are not limited to, all of the areas identified in Table 1, any structural controls, BMPs, accessible outfalls, and employee training records. At the time the audit is conducted, an annual compliance questionnaire will be completed by all tenants and included with the SWPPP as Appendix G. At the completion of the annual audit, a report will be drafted that includes the date of the evaluation, personnel conducting the evaluation, and any non-compliance observed. If non-compliances are observed, action to

correct the issue will be initiated within 60-days. Any failure to correct any identified issues is a violation of the Stormwater Permit. Once compliance is obtained, the personnel conducting the evaluation will include a certificate of compliance in the annual audit report. The annual compliance report will be attached to the SWPPP as Appendix H.

An annual facility audit will be conducted and documented for non-stormwater or unauthorized discharges. Any non-stormwater discharges not currently listed in section 3.2 of this program discovered shall be promptly corrected. Documentation of the location, source, and corrective actions taken to prevent the identified non-stormwater discharge shall be included with the SWPPP.

5.3 Enforcement

The Director of Aviation has the enforcement authority provided for in Title 20 of the Clark County Code to enforce compliance with all applicable Airport Rules and Regulations and Operating Directives. Operating Directive 01-6 enables the DOA ES&RM personnel to issue a Notice of Violation and up to a \$1,000.00 fine per day to any tenant found to be in non-compliance.


6.0 Recordkeeping

All records related to the SWPPP shall be maintained by the DOA ES&RM Section for a minimum of three years. These records are available upon request.

7.0 Certification


The following is required by the Nevada Division of Environmental Protection as stated in section IV.B.1.d Certification in the Stormwater General Permit NVR050000.

I, Charles A. Giesler, certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. I also confirm that a Stormwater Pollution Prevention Plan (SWPPP) has been completed, will be maintained on-site, and that the SWPPP will be compliant with any applicable local sediment and erosion control plans. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines for knowing violations.



Charles A. Giesler, CSP, CEM
Environmental, Safety, & Risk Management Administrator

Appendix A
General Storm Water Permit and NDEP Approval Letter



STATE OF NEVADA

Department of Conservation & Natural Resources

DIVISION OF ENVIRONMENTAL PROTECTION

Jim Gibbons, Governor

Allen Biaggi, Director

Leo M. Drozdoff, P.E., Administrator

Stormwater General Permit NVR050000

In compliance with the provisions of the Federal Clean Water Act as amended (33 U.S.C. 1251 et seq: the "Act") and Chapter 445A of the Nevada Revised Statutes, eligible dischargers who have submitted a Notice of Intent, filing fee, and have a Stormwater Pollution Prevention Plan(s) completed, implemented and maintained on the Permittee's site location in accordance with this permit, are authorized to discharge

Stormwater Associated with Industrial Activity


To Waters of the United States

in accordance with the conditions set forth in Parts I through IV hereof.

This permit shall become effective on September 22, 2008.

This permit and the authorization to discharge shall expire at midnight September 21, 2013.

Signed this 22nd day of September, 2008.



Steve McGoff, P.E.
Staff Engineer III
Bureau of Water Pollution Control

PART I. SPECIFIC PERMIT CONDITIONS

I.A PERMIT COVERAGE

- I.A.1 Objective.** The objective of this general permit is to control and reduce pollution to Waters of the U.S. from stormwater discharges associated with industrial activity through the use of **Best Management Practices ("BMPs")**.
- I.A.2 Stormwater Discharge Associated with Industrial Activity** is defined at 40 CFR §122.26(b)(14). This subject is discussed in more detail in Part I.A.5.b of this general permit.
- I.A.3 Waters of the U.S.** is defined at 40 CFR §122.2. This definition and other definitions pertinent to this permit can be found in Appendix A. Discharges to storm drain systems that in turn discharge to Waters of the U.S. are considered to be discharges to Waters of the U.S. The **U.S. Environmental Protection Agency ("EPA")** has delegated responsibility to the State of Nevada to implement the **National Pollutant Discharge Elimination System ("NPDES")** program authorized by the **Clean Water Act ("CWA")**. The NPDES permits regulate discharges to Waters of the U.S., which include surface Waters of the State. Nevada issues NPDES permits for discharges, including stormwater runoff, to surface waters, including lakes, streams, dry washes and storm drains.
- I.A.4 Best Management Practice** is defined by 40 CFR §122.2 as schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the pollution of Waters of the United States. BMPs also include treatment requirements, operating procedures, and practices to control plant site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage. In addition the term shall include erosion and sediment controls, stormwater conveyance, stormwater diversion, treatment structures, and any procedure or facility used to minimize the exposure of pollutants to stormwater or to remove pollutants from stormwater.
- I.A.5 Eligibility, Request for Inclusion, Continuation of Coverage**
- I.A.5.a Eligibility:** This general permit authorizes Stormwater Discharges Associated with Industrial Activity to Waters of the U.S. as defined by certain sectors within 40 CFR §122.26(b)(14).

I.A.5.b Stormwater Discharges Associated with Industrial Activity for this permit is defined as:

- I.A.5.b.(i) Facilities subject to stormwater effluent limitations guidelines, new source performance standards, or toxic pollutant effluent standards under 40 CFR subchapter N (except facilities with toxic pollutant effluent standards which are exempted under category (x) in this section);
- I.A.5.b.(ii) Facilities classified as **Standard Industrial Classifications ("SIC")** 24 (except 2434), 26 (except 265 and 267), 28 (except 283), 29, 311, 32 (except 323), 33, 3441, 373;
- I.A.5.b.(iii) Facilities classified as SIC 11 through 14 (mineral industry) including active or inactive mining operations (except for certain areas of coal mining operations no longer meeting the definition of a reclamation area under 40 CFR 434.11(1), or except for areas of non-coal mining operations which have been released from applicable State or Federal reclamation requirements after December 17, 1990) and oil and gas exploration, production, processing, or treatment operations, or transmission facilities that discharge stormwater contaminated by contact with or that has come into contact with, any overburden, raw material, intermediate products, finished products, byproducts or waste products located on the site of such operations; (inactive mining operations are mining sites that are not being actively mined, but which have an identifiable owner/operator; inactive mining sites do not include sites where mining claims are being maintained prior to disturbances associated with the extraction, beneficiation, or processing of mined materials, nor sites where minimal activities are undertaken for the sole purpose of maintaining a mining claim);
- I.A.5.b.(iv) Hazardous waste treatment, storage, or disposal facilities, including those that are operating under interim status or a permit under subtitle C of **Resource Conservation and Recovery Act ("RCRA")**;
- I.A.5.b.(v) Landfills, land application sites, and open dumps that receive or have received any industrial wastes (waste that is received from any of the facilities described under this subsection) including those that are subject to regulation under subtitle D of RCRA;
- I.A.5.b.(vi) Facilities involved in the recycling of materials, including metal scrap yards, battery re-claimers, salvage yards, and automobile junkyards, including but limited to those classified as SIC 5015 and 5093;

- I.A.5.b.(vii) Steam electric power generating facilities, including coal handling sites;
- I.A.5.b.(viii) Transportation facilities classified as SIC 40, 41, 42 (except 4221-25), 43, 44, 45, and 5171 which have vehicle maintenance shops, equipment cleaning operations, or airport deicing operations. Only those portions of the facility that are either involved in vehicle maintenance (including vehicle rehabilitation, mechanical repairs, painting, fueling, and lubrication), equipment cleaning operations, airport deicing operations, or which are otherwise identified under paragraphs (b)(14) (i)-(vi) or (viii)-(ix) of this section are associated with industrial activity;
- I.A.5.b.(ix) Treatment works treating domestic sewage or any other sewage sludge or wastewater treatment device or system, used in the storage treatment, recycling, and reclamation of municipal or domestic sewage, including land dedicated to the disposal of sewage sludge that are located within the confines of the facility, with a design flow of 1.0 million gallons per day or more, or required to have an approved pretreatment program under 40 CFR part 403. Not included are farm lands, domestic gardens or lands used for sludge management where sludge is beneficially reused and which are not physically located in the confines of the facility, or areas that are in compliance with section 405 of the CWA; and,
- I.A.5.b.(x) Facilities under SIC 20, 21, 22, 23, 2434, 25, 265, 267, 27, 283, 285, 30, 31 (except 311), 323, 34 (except 3441), 35, 36, 37 (except 373), 38, 39, and 4221-25.
- I.A.5.c This permit does not authorize stormwater discharges from the following:**
- I.A.5.c.(i) Mineral Industry Facilities defined within SIC code 10 under Category III of 40 CFR §122.26(b)(14). These discharges are authorized under Permit NVR300000; or
- I.A.5.c.(ii) Construction activity defined under Category (x) of 40 CFR §122.26(b)(14). These discharges are authorized under Permit NVR100000.
- I.A.5.d Request for Inclusion**
- I.A.5.d.(i) Eligible dischargers seeking authorization to discharge under this general permit shall electronically submit a completed **Notice of Intent ("NOI")**. The NOI can be found on the **Nevada Division of Environmental Protection's ("NDEP" or "the Division")** stormwater website at: http://ndep.nv.gov/bwpc/storm_ind03.htm. A completed NOI

confirmation page with an original signature by a qualified individual as discussed in Part IV.B and the applicable filing fee shall be submitted to NDEP. Provisional authorization begins 24 hours after a completed NOI is submitted electronically to NDEP. Following review of the NOI, NDEP may either: determine the NOI is complete and confirm coverage by providing a notification and an approval; determine the NOI is incomplete and deny coverage until a completed NOI is submitted; or deny coverage and require an application for an individual permit be submitted. Application deadlines are as follows:

- I.A.5.d.(i).(a) **Existing Industrial Facilities** - Facilities that are authorized under the existing NPDES permit for discharges associated with industrial activity shall submit a renewal NOI within ninety (90) days following the effective date of this permit to continue coverage under this new general permit.
- I.A.5.d.(i).(b) **New Industrial Facilities** - An NOI shall be submitted electronically at least twenty-four (24) hours before a discharge of stormwater associated with industrial activity occurs. The site is covered provisionally under this permit once the NOI has been received electronically by NDEP and until approval of the permit by NDEP.
- I.A.5.d.(i).(c) **New Owner or Operator** - Permit coverage may not be transferred. When the ownership of a facility changes, the new owner or operator of the facility shall submit an NOI at least 10 calendar days before the change in ownership. In conjunction with the filing of the NOI by the new owner or operator, the previous owner or operator shall submit a **Notice of Termination ("NOT")** at least ten (10) days before the change in ownership. Operators are defined as individuals that have the day-to-day operational control of those activities at the facility necessary to ensure compliance with the **Stormwater Pollution Prevention Plan ("SWPPP")** requirements or other permit conditions.

I.A.5.e Terminating Coverage

- I.A.5.e.(i) A Permittee may terminate coverage under this general permit by providing an NOT on a form approved by NDEP. Authorization to discharge terminates at midnight on the day that an NOT is postmarked for delivery to NDEP. If NDEP provides for an electronic submission of an NOT during the term of this permit, authorization to discharge terminates twenty-four (24) hours following receipt of the electronic NOT form by NDEP. An NOT shall be submitted either:

- I.A.5.e.(i).(a) Within ten (10) days after the facility ceases discharging stormwater associated with industrial activity;
- I.A.5.e.(i).(b) Obtains coverage under an individual permit;
- I.A.5.e.(i).(c) Obtains coverage under an alternative general permit; or
- I.A.5.e.(i).(d) Within ten (10) days before transfer of ownership or responsibility of the facility.

I.A.5.f Authorization

- I.A.5.f.(i) Eligible dischargers shall be included in this permit effective upon the authorization date.
- I.A.5.f.(ii) The authorization date shall be:
 - I.A.5.f.(ii).(a) The date the NOI and filing fee are received and approved by NDEP, or
 - I.A.5.f.(ii).(b) The effective date of this general permit for all holders of expired general permit NVR050000 that have submitted a new NOI for continued coverage under this permit.
- I.A.5.f.(iii) An authorization letter will be sent to the general permit holder stating the authorization date. Special conditions may be included.
- I.A.5.f.(iv) During the period beginning on the authorization date and lasting until permit coverage is terminated, the Permittee is authorized to discharge:
 - I.A.5.f.(iv).(a) Stormwater associated with industrial activity(ies) to Waters of the U.S. in accordance with the requirements of the SWPPP and the conditions of this permit.

I.A.5.g Miscellaneous Non-Stormwater Discharges:

- I.A.5.g.(i) Permittees authorized under this general permit may be authorized for certain miscellaneous non-stormwater discharges if those discharges are not significant contributors of pollutants. Such discharges may include: discharges from fire hydrant flushing; waters used to wash vehicles where detergents are not used; water used to control dust; potable water sources including waterline flushing; routine external building wash down which does not contain detergents; pavement wash water where spills or leaks of

toxic or hazardous materials have not occurred (unless all spilled material has been removed) and where detergents are not used; air conditioning condensate; uncontaminated groundwater or spring water; and foundation or footing drains where flows are not contaminated with process materials such as solvents. BMPs shall be implemented if needed to minimize impacts from these discharges. Non-stormwater discharges that are significant contributors of pollutants shall be eliminated or authorized under a separate NPDES permit. Although fire-fighting drainage may contain significant pollutant concentrations, the frequency of occurrence is low and the discharge is hereby authorized out of necessity.

I.A.5.h Requirement for Individual Permit:

I.A.5.h.(i) NDEP may require the holder of a permit to apply for and obtain an individual permit in accordance with Nevada Administrative Code ("NAC") 445A.269.

I.A.5.i NOI Requirements

I.A.5.i.(i) The minimum information required on a NOI shall consist of:

I.A.5.i.(i).(a) The facility name and mailing address of the facility filing for permit coverage;

I.A.5.i.(i).(b) The name, phone number and email address of the person responsible for implementing the SWPPP and complying with the terms of this general permit;

I.A.5.i.(i).(c) The county where the facility is located and the primary SIC code that best describes the industrial activity of the facility;

I.A.5.i.(i).(d) The name of the receiving water for the stormwater discharge;

I.A.5.i.(i).(e) Location for viewing the SWPPP, including the address and the contact information for the person responsible for implementing the SWPPP and complying with the terms of this general permit;

I.A.5.i.(i).(f) Information about the owner of the facility including the company name and mailing address of the facility and information about the owner including name, mailing address, phone number and the legal status of the owner (e.g. federal, state, tribal, private or public entity);

I.A.5.i.(i).(g) Information about the operator, including the company name and mailing address of the facility and information about the operator

including name, mailing address, phone number and the legal status of the operator (e.g. federal, state, tribal, private or public entity;

- I.A.5.i.(i).(h) Information where the annual billing/invoicing should be sent;
- I.A.5.i.(i).(i) Information about additional contacts;
- I.A.5.i.(i).(j) The opportunity to apply for a No-Exposure Exclusion. This is discussed in more detail in Part II.B.1.n.(iii) of this general permit; and
- I.A.5.i.(i).(k) A certification that a SWPPP has been developed and implemented according to the provisions of this permit.

I.A.5.j Notice of Change ("NOC") Requirements

- I.A.5.j.(i) If the owner or operator becomes aware that it failed to submit any relevant facts, or submitted incorrect information, in an NOI, the correct information shall be provided to the Division in an NOC within fourteen (14) days after discovery of the omission. If relevant information provided in the NOI changes (for example, phone number or P.O. Box number) an NOC shall be submitted within 14 days of the change.

I.A.5.k NOT requirements

- I.A.5.k.(i) The minimum information required on an NOT consists of:
 - I.A.5.k.(i).(a) Information requesting whether the operations associated with the permit have been terminated in accordance with applicable permit conditions;
 - I.A.5.k.(i).(b) Stormwater general permit number (ISW-xxxx);
 - I.A.5.k.(i).(c) Date the project was completed or terminated;
 - I.A.5.k.(i).(d) Facility operator information including name, mailing address, city, state, zip code and phone number;
 - I.A.5.k.(i).(e) Facility/site location information including name, physical address, city, state, zip code and phone number; and,
 - I.A.5.k.(i).(f) Certification statement signed and dated by the Permittee. The certification statement states:

“I certify under penalty of law that all stormwater discharges associated with industrial activity from the identified facility that was authorized by this general permit have been eliminated or that I am no longer the operator of the facility or construction site. I understand that by submitting this notice of termination, I am no longer authorized to discharge stormwater associated with industrial activity under this general permit, and that discharging pollutants in stormwater associated with industrial activity to Waters of the United States is unlawful under the Clean Water Act where the discharge is not authorized by an NPDES permit. I also understand that the submittal of this Notice of Termination does not release an operator from liability for any violations of this permit or the Clean Water Act.”

I.A.5.1 Address for Submittals:

I.A.5.1.(i) All NOIs, NOCs, NOTs, filing fees and any other information required by this permit or NDEP shall be submitted to the following address:

Stormwater Coordinator
Bureau of Water Pollution Control
Nevada Division of Environmental Protection
901 S. Stewart St., Suite 4001
Carson City, NV 89701

PART II. STORMWATER POLLUTION PREVENTION PLAN

II.A GENERAL REQUIREMENTS

II.A.1 The Permittee shall prepare and implement a SWPPP that complies with the terms of this permit for the permitted facility before submitting an NOI for permit coverage. The SWPPP does not need to be submitted to NDEP for review. If a SWPPP was prepared under the previous general permit, the permittee shall review and update it to meet all provisions of this new general permit prior to submitting a renewal NOI. All SWPPPs shall include BMPs, economically reasonable and appropriate in light of current industry practices that have been selected, designed, installed, implemented and maintained in accordance with good engineering practices to prevent or minimize all pollutants in your stormwater discharge, as well as any more stringent measures necessary to meet any water quality provisions of Part II.B.1.f, Part II.B.1.g and Part IV.A.3 of this general permit. NDEP does not currently require the Permittee to use a registered professional engineer or other qualified professional to prepare the SWPPP.

However, the person preparing the SWPPP shall be qualified to ensure all the requirements of the SWPPP are met.

II.A.2 A copy of the confirmation page from the NOI submittal and the permit approval letter received from NDEP shall be included in the SWPPP.

II.A.3 In general, the SWPPP shall:

- Identify all potential sources of pollution that may reasonably be expected to affect the quality of stormwater discharges from the permitted facility;
- Describe and ensure implementation of practices the Permittee will use to eliminate or reduce all pollutants in stormwater discharges from the permitted facility;
- Ensure compliance with the terms and conditions of this permit;
- Include all necessary measures to ensure that the discharge complies with all water quality provisions of Part II.B.1.f, Part II.B.1.g and Part IV.A.3 of this permit.
- The SWPPP shall be prepared in accordance with good engineering practice and shall consist of project information, BMPs that will be used at the site, an inspection and maintenance program, presence of non-stormwater discharges and BMPs for such discharges, and a description of any permanent stormwater controls.

II.A.4 Each of the plan elements in the SWPPP shall be revised as necessary to maintain accuracy if there are changes in design, components, or process if the SWPPP is found to be insufficient.

II.A.5 The Permittee shall review and amend the SWPPP as appropriate whenever there is: construction or a change in design, operation or maintenance at the permitted facility such that these situations have a significant impact on the discharge, or potential for discharge, of pollutants from the permitted facility; whenever a routine inspection or compliance evaluation determines deficiencies in any of the BMPs; whenever an inspection by a local or State inspector determines that modifications to the SWPPP are necessary; whenever there is a spill, leak or other release from the permitted facility; or any time there is an unauthorized discharge from the permitted facility.

II.A.6 Modifications to a SWPPP shall be made within fourteen (14) calendar days after discovery, observation or event requiring a SWPPP modification. Implementation of new or modified BMPs shall be initiated before the next storm event if possible, but no later than sixty (60) calendar days after discovery, or as otherwise provided or approved by NDEP. The amount of time taken to modify a BMP or implement additional BMPs shall be documented in the SWPPP.

II.A.7 The Permittee shall be required to make SWPPPs available upon request by NDEP or the State or local agency approving sediment and erosion plans, or stormwater management plans; local government officials; or the operator of a **municipal separate storm sewer system ("MS4")** receiving discharges from the site. If requested by the aforementioned parties, the Permittee shall provide the SWPPP prior to the time of an on-site inspection. Also, a copy of the SWPPP shall be provided to any member of the public who makes such a request in writing. **Confidential Business Information ("CBI")** may not be withheld from regulatory agencies, but may be withheld from the public. All portions of the SWPPP not justifiably considered CBI shall be provided to the public upon written request.

II.A.8 The Permittee shall establish a **pollution prevention team ("PPT")** and list the staff members (either by name or title) that comprise the facility's stormwater PPT. The PPT is responsible for assisting the facility manager in developing, implementing, maintaining, revising and ensuring compliance with the permitted facility's SWPPP. Specific responsibilities of each staff individual on the team shall be identified and listed in the SWPPP. Each member of the stormwater PPT shall have ready access to either an electronic or paper copy of applicable portions of this permit and the SWPPP.

II.B SPECIFIC REQUIREMENTS

II.B.1 The SWPPP shall include the following minimum elements:

II.B.1.a Facility Identification:

II.B.1.a.(i) Facility Name;

II.B.1.a.(ii) Facility Location: Address, City, State, Zip Code, and County;

II.B.1.a.(iii) Permittee: Company or agency mailing address and phone number;

II.B.1.a.(iv) Contact information: Name, street address, city, state, zip code, and phone number; and,

II.B.1.a.(v) Person(s) responsible for implementation of plan and complying with the terms of this permit.

II.B.1.b Facility Characteristics

- II.B.1.b.(i) Provide a description of the nature of the industrial activities at the permitted facility.
- II.B.1.b.(ii) Provide an estimate of the percent of impervious surface at the facility using the following formula:
- $((\text{Area of Roofs} + \text{Area of Pavement and Other Impervious Surfaces}) / \text{Total Area of the Facility}) \times 100$
- II.B.1.b.(iii) Provide average annual precipitation for your locale. This information can be obtained from almanacs or the closest airport. Note which months or seasons are usually the wettest and include such details as expected rainfall and storm intensity (e.g. wet season: November – March; typical amount: 0.5 – 2 inches over 2 hours)
- II.B.1.b.(iv) Identify actual and potential sources of pollution that may reasonably be expected to affect the quality of stormwater discharges from the facility;
- II.B.1.b.(v) Establish BMPs that will prevent or minimize pollution in stormwater discharges from the facility and ensure compliance with the terms and conditions of this general permit;
- II.B.1.b.(vi) Describe how the selected practices and controls are appropriate for the facility and how each will effectively prevent or lessen pollution;
- II.B.1.b.(vii) Discuss how the BMPs relate to each other such that together they comprise an integrated, facility-wide approach for pollution prevention in stormwater discharges. The discussion may include references to literature or site-specific performance information on the selected controls and practices to demonstrate the appropriateness of each.

II.B.1.c General Location Map

- II.B.1.c.(i) Provide a general location map (e.g., a U.S. Geological Survey quadrangle map), with enough detail to identify the location of the facility and the receiving waters.

II.B.1.d Site Map

- II.B.1.d.(i) A site map(s) shall be developed that depicts the following:
- II.B.1.d.(i).(a) The size of the property in acres;

- II.B.1.d.(i).(b) Location and extent of significant structure and impervious surfaces;
- II.B.1.d.(i).(c) The location of each outfall covered by the permit;
- II.B.1.d.(i).(d) An outline of the drainage area and direction of flow (use arrows) that is within the facility's boundary and that contributes stormwater to each permitted outfall;
- II.B.1.d.(i).(e) Locations of connections or discharges to an MS4, including ditches, pipes and swales;
- II.B.1.d.(i).(f) Locations of all structures (e.g. buildings, garages, storage tanks);
- II.B.1.d.(i).(g) Listing and location of all existing source and structural control BMPs that are designed to reduce pollution in stormwater runoff;
- II.B.1.d.(i).(h) Location of any process wastewater treatment units (including ponds);
- II.B.1.d.(i).(i) Location of a bag house and other air treatment units exposed to precipitation or runoff;
- II.B.1.d.(i).(j) Location of surface water bodies (including wetlands) within one (1) mile of the facility, including all receiving waters for the stormwater discharge from the facility;
- II.B.1.d.(i).(k) Location of vehicle and equipment maintenance areas and/or cleaning areas;
- II.B.1.d.(i).(l) Location of physical features of the site that may influence stormwater runoff or contribute a dry weather flow;
- II.B.1.d.(i).(m) Location of processing areas; storage areas; material loading/unloading areas; fueling stations; access roads, rail cars and tracks; and other locations where significant materials are exposed to precipitation or runoff;
- II.B.1.d.(i).(n) Locations and sources of run-on to the facility from adjacent property that contains significant quantities of pollutants. An evaluation of how the quality of the stormwater running onto the facility impacts the stormwater discharges from the facility;
- II.B.1.d.(i).(o) Identify any storage piles containing salt used for road de-icing or other commercial or industrial purposes; and
- II.B.1.d.(i).(p) The site map shall show the flow of stormwater runoff from each of

these locations so that the final outfall where the discharge leaves the facility's boundary is apparent.

II.B.1.e Non-Stormwater Discharges

- II.B.1.e.(i) All non-stormwater discharges discussed in Part I.A.5.g.(i) that qualify for permit coverage shall be identified in the SWPPP. The SWPPP shall describe the discharge points and appropriate BMPs for these non-stormwater discharges.
- II.B.1.e.(ii) A survey of potential non-stormwater sources shall be conducted and documented at a minimum of once per calendar year.
- II.B.1.e.(iii) The on-site storm sewer system shall be tested or inspected (e.g. screened for dry weather flows) for the presence of non-stormwater flows at a minimum of once per quarter.
- II.B.1.e.(iv) Procedures shall be evaluated and implemented to eliminate any potential sources that are discovered and not permitted.
- II.B.1.e.(v) The SWPPP shall ensure that non-stormwater sources are not combined with stormwater discharges from the facility, and are not allowed to enter the separate storm sewer system, unless they are authorized by the Division.
- II.B.1.e.(vi) Non-stormwater discharges to Waters of the U.S. that are not authorized by an NPDES permit are unlawful and shall be eliminated.

II.B.1.f Receiving Waters

- II.B.1.f.(i) The SWPPP shall include the name(s) of all surface waters that receive discharges from the facility. If the facility discharges through any MS4, the permittee shall identify the MS4 operator(s), and the receiving water to which the MS4 discharges.

II.B.1.g Discharges to Water Quality Impaired Waters

- II.B.1.g.(i) When discharges to water quality-impaired waters that are contained in the current 303(d) Impaired Water Body listing issued by NDEP's Bureau of Water Quality Planning, the permittee must investigate whether discharges from the permittee's site will contribute significantly to any 303(d) listing. When the permittee discharges into a water body with an established **Total Maximum Daily Load ("TMDL")**, the permittee shall comply with all

applicable TMDL requirements. Information concerning the 303(d) list can be found on the following NDEP website:
<http://ndep.nv.gov/bwqp/303dlist.htm>. For a list of TMDLs approved by EPA please refer to the following NDEP website:
<http://ndep.nv.gov/bwqp/tmdl.htm>.

- II.B.1.g.(ii) When a TMDL has not been established as described in the previous section, the permittee must include a section in the SWPPP describing the condition for which the water has been listed. The SWPPP must also include a demonstration that the BMPs that are selected for implementation will be sufficient to ensure that the discharges will not cause or contribute to an exceedance of an applicable State water quality standard. The SWPPP shall document any consultation with state authorities on water quality impairment-related requirements and activities.

II.B.1.h Description of Potential Pollutants and Sources

- II.B.1.h.(i) The description of potential pollutant sources shall identify each area at the facility where industrial materials or activities are exposed to stormwater. Industrial materials and activities include, but are not limited to: material handling equipment or activities; industrial machinery; raw materials; industrial production and processes; intermediate products; by-products, final products and waste products. Material handling activities include, but are not limited to: the storage, loading and unloading, transportation, disposal or conveyance of any raw material, intermediate product, final product and waste product. For each area identified, the description shall include, at a minimum:

- II.B.1.h.(i).(a) **Activities in the area.** A narrative description shall be developed to describe all activities (e.g. material storage, equipment fueling and cleaning, cutting steel beams) and potential sources of pollutants that may reasonably be expected to add pollutants to stormwater discharges or that may result in dry weather discharges from the storm sewer system.

- II.B.1.h.(i).(b) **Pollutants.** For each identified activity above, list the associated pollutant(s) or pollutant constituent(s) (e.g. crankcase oil, zinc, sulfuric acid, cleaning solvents). The pollutant list shall include all significant materials handled, treated, stored or disposed that have been exposed to stormwater in the three (3) years prior to the date the permittee prepared or amended the SWPPP. The list shall include any hazardous

substances or oil at the facility, and any materials stored in drums, barrels, tanks, and similar containers;

II.B.1.h.(i).(c)

Spills and Leaks. The permittee shall identify where potential spills and leaks could occur that would contribute pollutants to stormwater discharges and the corresponding outfalls. The permittee shall document in the SWPPP all significant spills and leaks of toxic or hazardous pollutants that actually occurred at exposed areas or that drained to a stormwater conveyance in the three (3) years prior to the date the permittee prepared or amended the SWPPP.

Significant spills and leaks include, but are not limited to: releases of oil or hazardous substances in excess of quantities that are reportable under CWA §311 (see 40CFR 110.6 and 40 CFR 117.21) or Section 102 of the **Comprehensive Environmental Response, Compensation and Liability Act ("CERCLA")**. Significant spills may also include releases of oil or hazardous substances that are not in excess of reporting requirements. This permit does not relieve the Permittee of the reporting requirements of 40 CFR 110, 40 CFR 117 and 40 CFR 302 relating to spills or other releases of oils or hazardous substances.

II.B.1.h.(i).(d)

The above information shall be updated within fourteen (14) days following a significant change in the types of materials that are exposed to precipitation or runoff, or significant changes in material management practices that may affect the exposure of materials to precipitation or runoff.

II.B.1.i

Certification Concerning the Presence of Non-Stormwater Discharges

II.B.1.i.(i)

The SWPPP shall include a certification that all discharges (i.e., outfalls) have been tested or evaluated for the presence of non-stormwater, and that all unauthorized discharges have been eliminated. The certification shall be signed in accordance with Part IV.B.1 of this permit and shall include:

II.B.1.i.(i).(a)

Documentation of how the evaluation was conducted, a description of the results of any test and/or evaluation for the presence of non-stormwater discharges (i.e. identification of unauthorized discharge(s) origin and composition results of any testing), dates of evaluations or tests, and the points in the separate storm sewer system that were observed during the investigation;

- II.B.1.i.(i).(b) A list of the outfalls or onsite drainage points that were directly observed during the test;
- II.B.1.i.(i).(c) The action(s) taken to eliminate unauthorized discharge(s), if any were identified. For example, a floor drain was sealed, a sink drain was rerouted to sanitary, or an NPDES permit application was submitted for a cooling water discharge; and
- II.B.1.i.(i).(d) The investigation for non-stormwater discharges shall be completed and the certification shall be prepared and made readily available for review by authorized NDEP personnel upon request.
- II.B.1.i.(ii) Failure to Certify:
- II.B.1.i.(ii).(a) If a part of the on-site storm sewer system can not be reasonably accessed to complete the evaluation, certification shall be provided for the remainder of the system.
- II.B.1.i.(ii).(b) Notice of this deficiency shall be provided to NDEP within one hundred eighty (180) days after the NOI is submitted.
- II.B.1.i.(ii).(c) Facilities that contribute non-stormwater discharges to an MS4 shall provide notice of this deficiency to NDEP and the MS4.
- II.B.1.i.(ii).(d) The notice shall include an explanation of why the evaluation could not be performed and a list of all known potential, non-permitted, non-stormwater sources that could not be included in the certification.

II.B.1.j Stormwater Control Measures

- II.B.1.j.(i) The permittee shall implement BMPs for all areas identified in Part II.B.1.d to prevent or minimize pollutants in stormwater discharges from the facility. The permittee shall also take all reasonable steps to control or address the quality of discharges from your site that may not originate at the permitted facility. In the SWPPP describe the type, location and implementation of all BMPs for each area where industrial materials or activities are exposed to stormwater. The permittee shall describe the stormwater runoff management practices, i.e., permanent structural BMPs for the facility in the SWPPP. These are typically used to divert, infiltrate, reuse, contain or otherwise reduce pollutants in your discharges. Such BMPs may be required by local authority. Structural BMPs associated with wetlands may require a separate permit under section 404 of the CWA before installation. Flow velocity dissipation devices shall be

placed at discharge locations and along the length of any outfall channel if the flows would otherwise create erosive conditions. Discharge velocities shall be controlled to the extent necessary to prevent the destruction of the natural physical characteristics of receiving waters by erosion. Velocity dissipation devices may be constructed at discharge points or along channels and other stormwater collection areas that lead to outfalls. Management alternatives to minimize runoff, such as limiting impervious cover, may also be considered.

II.B.1.j.(ii)

Consider the following when selecting BMPs:

- Preventing stormwater from coming into contact with polluting materials is much more effective than trying to remove pollutants from stormwater;
- BMPs generally must be used in combination with each other for most effective water quality protection;
- The type and quantity of pollutants, including their potential to impact receiving water quality;
- Minimizing impervious areas at the facility will reduce runoff and improve groundwater recharge and stream base flows in local streams (taking into account the potential for groundwater contamination);
- Flow attenuation by use of open vegetated swales and natural depressions;
- Diverting flow from areas of materials handling, storage or use;
- Conservation or restoration of riparian buffers;
- Infiltration of runoff onsite, (including bio-retention cells, green roofs, and pervious pavement); and
- Treatment interceptors (e.g., swirl separators and sand filters).

II.B.1.j.(i)

The permittee shall implement appropriate BMPs to prevent and minimize pollutants in stormwater discharges from the facility, unless the permittee demonstrates that such controls are not relevant to discharge (e.g., there are no storage piles containing salt) from the facility. The permittee shall keep abreast of new BMPs or new applications of existing BMPs for the most effective means of achieving water quality protection, and include these in your SWPPP as appropriate.

II.B.1.k

Erosion and Sedimentation Controls

II.B.1.k.(i)

A section within the SWPPP shall be developed to address soil erosion. Erosion prevention measures and controls shall be evaluated and implemented as necessary to reduce soil erosion in areas of the facility that

have ongoing erosion or potential for soil erosion. The following controls shall be evaluated, at a minimum: soil stabilization through vegetative cover; contouring slopes; paving; and installation of structural controls.

II.B.1.l Structural Controls

II.B.1.l.(i) Physical structures shall be evaluated annually and installed along with other pollution prevention measures and controls, as necessary, to reduce pollutants in stormwater discharges. Examples of structural controls that may be utilized include vegetated swales, oil/water separators, settling ponds, and other physical structures.

II.B.1.m Maintenance Program for Structural Controls

II.B.1.m.(i) A section within the SWPPP shall be developed to establish a maintenance program for stormwater structural controls. Oil/water separators, catch basins, sediment ponds, grass swales, berms, and other structural controls shall be inspected on a regular basis.

II.B.1.m.(ii) Maintenance frequencies shall be established for each of the controls at intervals that ensure effective operation. Mechanical equipment that is part of a structural control, such as a stormwater pump, shall be inspected at least one (1) time per year and maintained when necessary to prevent failures that could result in a discharge of pollutants. This section of the SWPPP shall identify qualified personnel to conduct inspections and establish inspection and maintenance schedules and state the justification for the frequency of the inspection and maintenance schedules. Records shall document the estimated volumes of solids removed from catch basins, sediment ponds, and other similar control structures, and that the solids have been properly disposed of in accordance with applicable federal, state and local law.

II.B.1.n Good Housekeeping Measures

II.B.1.n.(i) A section within the SWPPP shall be developed to ensure areas of the facility that contribute or potentially contribute pollutants to stormwater discharges (e.g. areas around trash dumpsters, storage areas, loading docks, and outdoor processing areas) are maintained in a clean and orderly manner; and,

II.B.1.n.(ii) Good housekeeping measures shall include measures to eliminate or reduce exposure of garbage and refuse materials to precipitation or runoff prior to their disposal. The permittee shall include a schedule for regular

pickup and disposal of waste materials , along with quarterly inspections for leaks and conditions of drums, tanks and containers; and

II.B.1.n.(iii) To the extent practicable, locate industrial materials and activities inside, or protect them with storm-resistant coverings to prevent exposure to rain, snow, snowmelt and runoff (although significant enlargement of impervious surface area is not recommended). **Note: If the permittee is able to eliminate exposure at all industrial areas, the facility may be eligible for the “No Exposure” exclusion and not need to have a permit (see 40 CFR 122.26(g) and the *Guidance Manual for Conditional Exclusion from Stormwater Permitting Based on “No Exposure” of Industrial Activities to Stormwater* found at www.epa.gov/npdes/stormwater).**

II.B.1.n.(iv) The good housekeeping measures shall be incorporated as a part of the employee training program.

II.B.1.o Spill Prevention and Response Measures

II.B.1.o.(i) A section within the SWPPP shall be developed and implemented to prevent spills and to provide for adequate spill response. This section shall:

II.B.1.o.(i).(a) Identify areas where spills could contribute pollutants to stormwater discharges;

II.B.1.o.(i).(b) Develop and implement procedures to minimize or prevent contamination of stormwater from spills (e.g. training equipment operators to inspect for leaks each day during operation of equipment; installation of secondary containment structures around liquid storage tanks and drums; installation of overfill prevention devices on pumps and tanks; modification of material handling techniques; and routine inspection of drums, tanks and other containers);

II.B.1.o.(i).(c) Require drums, tanks, and other containers to be clearly labeled and properly sealed or closed;

II.B.1.o.(i).(d) Require that hazardous waste containers that require special handling, storage, use, and disposal be clearly marked;

II.B.1.o.(i).(e) Develop and implement specific spill prevention and clean up techniques;

- II.B.1.o.(i).(f) Make the Spill Prevention and Response Measures document available to facility personnel materials and equipment necessary for spill clean up;
- II.B.1.o.(i).(g) Develop and maintain an inventory of spill cleanup materials and equipment; and
- II.B.1.o.(i).(h) Incorporate these measures as a part of the employee training program.

II.B.1.p Miscellaneous/Additional BMPs

- II.B.1.p.(i) A section within the SWPPP shall be developed to establish any other miscellaneous and/or additional BMPs not previously mentioned in other sections of the SWPPP to reduce the discharge and potential discharge of pollutants in stormwater. Development of BMPs shall be based on the activities and potentials for contamination that are identified in Part II.B.1.h of this general permit, "Description of Potential Pollutants and Sources;"
- II.B.1.p.(ii) The permittee shall have a preventive maintenance program in the SWPPP that discusses regular inspecting, testing, maintaining and repairing of all industrial equipment and systems to avoid situations that may result in leaks, spills and other releases. These measures are in addition to specific BMP maintenance as required under Part II.B.1.q (Maintenance of BMPs);
- II.B.1.p.(iii) Material handling and storage to minimize exposure of industrial materials shall be considered and included, where feasible;
- II.B.1.p.(iv) The permittee shall implement controls to ensure that no solid materials, including floatable debris, are discharged to Waters of the U.S., except as authorized by a permit issued under section 404 of the CWA;
- II.B.1.p.(v) The generation of dust, along with off-site vehicle tracking of raw, final or waste materials, or sediments, shall be minimized; and
- II.B.1.p.(vi) The introduction of raw, final or waste materials to exposed areas shall be minimized.
- II.B.1.p.(vii) For storage piles of salt or piles containing salt used for de-icing or other commercial or industrial purposes, the permittee shall enclose or cover these piles to prevent exposure to precipitation. The permittee shall implement appropriate measures (e.g., good housekeeping, diversions, containment) to minimize exposure resulting from adding to or removing

materials from the pile. Piles do not need to be enclosed or covered only if stormwater from the pile is not discharged directly or indirectly to Waters of the U.S. or discharges from the piles are authorized and controlled under another NPDES permit.

II.B.1.q Maintenance of BMPs

II.B.1.q.(i) All BMPs the permittee identifies in its SWPPP shall be maintained in effective operating condition. If site inspections required by Part III identify BMPs that are not operating effectively, maintenance shall be performed before the next anticipated storm event, or as necessary to maintain the continued effectiveness of stormwater controls. BMPs shall be maintained or replaced when the BMP reached fifty (50) percent of its operating capacity. If maintenance prior to the next anticipated storm event is impracticable, maintenance shall be scheduled and accomplished as soon as practicable. In the case of non-structural BMPs, the effectiveness of the BMP shall be maintained by appropriate means (e.g., spill response supplies available and personnel trained, etc.).

II.B.1.r Employee Training Program and Employee Education

II.B.1.r.(i) A section within the SWPPP shall be developed to establish a training program. Training shall be provided to all employees who are responsible for implementing or maintaining activities identified in the SWPPP. Employee training shall include, at a minimum:

II.B.1.r.(i).(a) Proper material management and handling practices for specific chemicals, fluids, and other materials used or commonly encountered at the facility;

II.B.1.r.(i).(b) Spill prevention methods;

II.B.1.r.(i).(c) The location of materials and equipment necessary for spill clean up;

II.B.1.r.(i).(d) Spill clean up techniques;

II.B.1.r.(i).(e) Proper spill reporting procedures; and

II.B.1.r.(i).(f) Familiarization with good housekeeping measures, BMPs, and goals of the SWPPP.

II.B.1.r.(iii) The schedule for employee training sessions shall be developed based on pollutant potential, employee turnover rate, and may include other factors.

- II.B.1.r.(iv) Training shall be conducted at least one (1) time per year and records of training activities shall be maintained in the SWPPP.
- II.B.1.r.(v) Education shall be provided at least once every five (5) years to those employees at the facility that are not directly responsible for implementing or maintaining activities identified in the SWPPP, and that do not participate in the employee training program. At a minimum, these employees shall be informed of the basic goal of the SWPPP.

II.B.1.s Records

- II.B.1.s.(i) Records for each element in Part II.B.1.j of "Stormwater Control Measures" shall be included and maintained as an attachment to the SWPPP. Records shall document and describe maintenance activities, inspections, spills, discharge quality, employee training activities, employee education activities, SWPPP updates/modifications, and other events relative to each element.

PART III. Inspections and Compliance Monitoring

III.A.1 Periodic Inspections

- III.A.1.a Qualified personnel, who are familiar with the industrial activities performed at the facility, shall conduct periodic inspections to determine the effectiveness of the Good Housekeeping Measures, Spill Prevention and Response Measures, Erosion Control Measures, Maintenance Program for Structural Controls, BMPs, and the Employee Training Program.
- III.A.1.b Periodic inspections shall be conducted on a frequency of once per quarter, at a minimum, relating to Specific Requirements for Industrial Activities.
- III.A.1.c The inspections shall be documented through the use of a checklist that is developed to include each of the controls and measures that are evaluated. The checklists shall be included in the SWPPP.
- III.A.1.d When revisions or additions to the SWPPP are recommended as a result of inspections, a summary description of these proposed changes shall be attached to the inspection checklist within fourteen (14) days. The summary shall identify any necessary time frames required to implement the proposed changes. The Permittee shall make the identified revisions as soon as practicable, but not later than sixty (60) calendar days after

discovery of the deficiency, or as otherwise provided or approved by NDEP.

III.A.2 Quarterly Visual Monitoring

III.A.2.a Stormwater discharges from each outfall authorized by this general permit shall be visually examined on a quarterly basis. Where practicable, the same individual should carry out the collection and examination of discharges for the entire permit term to ensure consistency. Monitoring shall be conducted during daylight hours, samples shall be examined in a well lit area, and findings shall document observations of color, clarity, floating solids, settled solids, suspended solids, foam, oil sheen, and other obvious indicators of stormwater pollution. Any noticeable odors shall also be noted. Some examinations, such as an examination for odor and foam, may necessarily be conducted immediately following collection of the sample. All examinations shall be performed within a time frame that ensures the sample is representative of the discharge.

III.A.2.b Records of quarterly visual monitoring shall include the date and time samples were collected and examined, names of personnel that collected and examined the samples, the nature of the discharge (e.g., runoff, snow melt), the magnitude of the storm that was sampled and the length of time since the last storm with a magnitude of at least 0.1 inch, and the visual quality of the stormwater discharge.

III.A.3 Comprehensive Site Compliance Evaluation

III.A.3.a Description

III.A.3.a.(i) The comprehensive site compliance evaluation is a required site inspection and an overall assessment of the effectiveness of the current SWPPP. This evaluation is in addition to other routine inspections required by the permit (e.g. inspections of good housekeeping measures, structural controls, and for identification of non-stormwater sources). This evaluation may, however, substitute for a periodic inspection if it is conducted during the regularly scheduled period for the periodic inspection.

III.A.3.b General Requirements

III.A.3.b.(i) The evaluation shall be conducted at least once per year by either one or more qualified employees or designated representatives, who are familiar with the industrial activities performed at the facility and the elements of the SWPPP. The evaluation shall include:

- III.A.3.a.(i).(a) Inspection of all areas identified in the Inventory of Exposed Materials section of the SWPPP;
- III.A.3.a.(i).(b) Inspection of all structural controls, including the maintenance and effectiveness;
- III.A.3.a.(i).(c) Inspection of all non-structural controls including BMP effectiveness, good housekeeping measures, and spill prevention;
- III.A.3.a.(i).(d) Inspection of all reasonably accessible areas immediately downstream of each stormwater outfall that is authorized under this general permit; and
- III.A.3.a.(i).(e) A review of all records required by this general permit.

III.A.3.c Site Compliance Evaluation Report

- III.A.3.c.(i) The report shall include a narrative discussion of the Permittee's compliance with the current SWPPP. The report shall document the personnel conducting the evaluation, the dates of the evaluation, and any incidents of non-compliance.
- III.A.3.c.(ii) For purposes of this inspection, a non-compliance incident is any instance where an element of the SWPPP is either not implemented, or where specific conditions of the permit are not met.
- III.A.3.c.(iii) If no incidents of non-compliance are discovered, the report shall contain a certification that the facility is in compliance with the SWPPP.
- III.A.3.c.(iv) If the report indicates an incident of non-compliance, the operator shall complete all necessary actions to come into compliance as soon as practicable, but no later than sixty (60) calendar days following the evaluation. Failure to take corrective action in the stipulated timeframe is a violation of this permit. Failure to implement a SWPPP in compliance with this permit requirements would be an independent violation during the full-time period in which the non-compliance existed;
- III.A.3.c.(v) The report shall either be included as a part of the SWPPP or referenced in the SWPPP and be made readily available for inspection and review by the Division upon request.

III.A.3.d Revision of the SWPPP

III.A.3.d.(i) The SWPPP shall be revised to include and address the findings of the Site Compliance Evaluation Report within fourteen (14) days following completion of the evaluation. Revisions shall include all applicable changes that result from the comprehensive site compliance report and all applicable updates to:

III.A.3.d.(i).(a) Elements of the SWPPP that require modification for effectiveness;

III.A.3.d.(i).(b) Any additional elements (e.g. structural controls or BMPs) that should be added or modified for prevention of pollution;

III.A.3.d.(i).(c) The site map;

III.A.3.d.(i).(d) The inventory of exposed materials;

III.A.3.d.(i).(e) The description of the good housekeeping measures;

III.A.3.d.(i).(f) The description of structural and non-structural controls; and

III.A.3.d.(i).(g) Any other element of the plan that was either found to be inaccurate or that will be modified.

III.A.3.e Inspection of the SWPPP On-Site

III.A.3.e.(i) The SWPPP shall be maintained, with a copy of this general permit at the site and be readily available for review by authorized NDEP personnel upon request. The SWPPP shall be modified as often as necessary. Each revision shall be dated and all revisions shall be retained according to Part II.B.1.s. NDEP may determine, following a review or site inspection that the SWPPP is not sufficient and require that the SWPPP be revised to correct all deficiencies.

III.A.4 General Monitoring and Records Requirements

III.A.4.a Representative Storm Events

III.A.4.a.(i) Monitoring, sampling, examinations, and inspections of stormwater discharges that are required as a provision of this general permit shall be conducted on discharges of runoff from a representative storm event. For the purposes of this general permit, a representative storm event is an event with at least 0.1 inch of measured precipitation that occurs with a

minimum interval from the preceding measurable storm of at least seventy-two (72) hours. The 72-hour interval is not required if either the preceding storm event did not yield a discharge that was sufficient for obtaining a sample, or if it is documented in the SWPPP that a less than 72-hour interval is representative for local storm events for the sampling period.

III.A.4.b Representative Discharges from Substantially Similar Outfalls

II.A.4.b.(i) If discharges of stormwater through two or more outfalls are substantially the same, sampling and monitoring may be conducted at one of the outfalls, and the results may be reported as representative of the discharge from the substantially similar outfall. Before results may be submitted as representative of discharges from substantially similar outfalls, the SWPPP shall include a description of outfall locations and provide justification of why the discharge qualities from the outfalls are substantially similar. To determine if outfalls are substantially similar, the following characteristics of each outfall shall be compared:

- III.A.4.b.(i).(a) The industrial activities that occur in the drainage area to each outfall;
 - III.A.4.b.(i).(b) Significant materials stored or handled within the drainage area to each outfall; and
 - III.A.4.b.(i).(c) The management practices and pollution control structures that occur within the drainage area of each outfall.
- II.A.4.b.(ii) Substantially similar outfalls may not be established for non-stormwater discharges.

III.A.4.c Sampling Data

III.A.4.c.(i) The following categories of facilities have stormwater effluent guidelines for at least one of their subcategories: cement manufacturing (40 CFR 411); feedlots (40 CFR 412); fertilizer manufacturing (40 CFR 418); petroleum refining (40 CFR 419); phosphate manufacturing (40 CFR 422); steam electric power generation (40 CFR 423); coal mining (40 CFR 434); mineral mining and processing (40 CFR 436); ore mining and dressing (40 CFR 440); paving and roofing materials (40 CFR 443); and landfills (40 CFR 445). A facility that falls into one of these general categories shall examine the applicable effluent guideline to determine if it is categorized in one of the subcategories that have storm water effluent guidelines. If a facility is classified as one of those subcategories, that facility is subject to

the standards listed in the CFR for that category, shall sample stormwater discharges from the facility, at a minimum, of one (1) time per calendar year;

- III.A.4.c.(ii) All lab analysis received from stormwater discharge samples shall be submitted to NDEP;
- III.A.4.c.(iii) If applicable, all data from the laboratory analyses of stormwater discharge samples shall be summarized;
- III.A.4.c.(iv) The summary shall be updated on an annual basis to include the results of all additional analyses;
- III.A.4.c.(v) The data summary shall either be included as an attachment to the SWPPP or may be referenced and maintained separately;
- III.A.4.c.(vi) NDEP may require stormwater discharge sampling by the permittee to determine compliance with the terms of this permit; and,
- III.A.4.c.(vii) If sampling is required, the sample shall be taken within the first thirty (30) minutes of the discharge where practicable. Where not practicable, the discharge shall be sampled within the first sixty (60) minutes.

PART IV. STANDARD CONDITIONS

IV.A OPERATING REQUIREMENTS

IV.A.1 Proper Operation and Maintenance

- IV.A.1.a The Permittee shall implement all BMPs used to comply with this permit and maintain them in good working order.

IV.A.2 Removed Substances

- IV.A.2.a Solids and other pollutants removed in the course of treatment or control of stormwater shall be disposed of in accordance with applicable laws, regulations, codes, and ordinances.

IV.A.3 Water Quality Standards

- IV.A.3.a There shall be no discharge of substances that cause or contribute to a violation of the water quality standards of the State of Nevada in accordance with Nevada Revised Statutes ("NRS") and NAC 445A.

IV.A.4 Sampling and Analysis

- IV.A.4.a If any samples or measurements are taken pursuant to this permit they shall be representative of the volume and nature of the discharge. Laboratory analyses shall be performed by a State of Nevada certified laboratory. Results from this lab shall be provided to the Division in accordance with this permit.

IV.A.5 Test Procedures

- IV.A.5.a Test procedures for analyses of pollutants shall conform to regulations (40 CFR § 136) published pursuant to Section 304(h) of the CWA, under which such procedures may be required, unless other procedures are approved by the Division.

IV.A.6 Recording the Results

- IV.A.6.a If any measurement or sample is taken pursuant to this permit, the Permittee shall record the following information:
- IV.A.6.a.(i) The exact place, date, and time of sampling;
 - IV.A.6.a.(ii) The dates the analyses were performed;
 - IV.A.6.a.(iii) The person(s) who performed the analyses;
 - IV.A.6.a.(iv) The analytical techniques or methods used; and
 - IV.A.6.a.(v) The results of all required analyses.

IV.A.7 Adverse Impact

- IV.A.7.a The Permittee shall take all reasonable steps to minimize any adverse impacts to receiving waters from any unauthorized discharge including monitoring as necessary to determine the nature and impact of the unauthorized discharge.

IV.B ADMINISTRATIVE REQUIREMENTS

IV.B.1 Signature Requirements

- IV.B.1.a **Notices of Intent:** All NOIs shall be signed as follows:
- IV.B.1.a.(i) By a responsible corporate officer. For the purpose of this section, a responsible corporate officer means:

- IV.B.1.a.(i).(a) A president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or
- IV.B.1.a.(i).(b) The manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
- IV.B.1.a.(ii) For a partnership or sole proprietorship: By a general partner or the proprietor, respectively; or
- IV.B.1.a.(iii) For a municipality, state, federal, or other public agency: By either a principal executive officer or ranking elected official. For purposes of this section, a principal executive officer of a federal agency includes:
- IV.B.1.a.(iii).(a) The chief executive officer of the agency, or
- IV.B.1.a.(iii).(b) A senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.
- IV.B.1.b **Duly Authorized Representative**
- IV.B.1.b.(i) All SWPPPs and any other information required by this permit or requested by NDEP shall be signed by a person described in this section, or by a duly authorized representative of that person. A person is a duly authorized representative only if:
- IV.B.1.b.(i).(a) The authorization is made in writing by a person described under Section II.B.1;
- IV.B.1.b.(i).(b) The authorization specifies either an individual or a position having responsibility for the overall operation of the facility or for environmental matters for the company; and

IV.B.1.b.(i).(c) The authorization is submitted to NDEP.

IV.B.1.c Changes to Authorization

IV.B.1.c.(i) If an authorization under Section IV.B.1 is no longer accurate because the individual or position has changed, a new written authorization shall be submitted to the Division prior to or together with any information signed by the new representative within thirty (30) days.

IV.B.1.d Certification

IV.B.1.d.(i) Any person signing a document under Section IV.B.1. shall make the following certification.

“I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. I also confirm that a stormwater pollution prevention plan (SWPPP) has been completed, will be maintained at the project site, and that the SWPPP will be compliant with any applicable local sediment and erosion control plans. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines for knowing violations.”

IV.B.3 Records Retention

III.B.3.a All records and information resulting from activities performed pursuant to this permit shall be retained for a minimum of three years after acceptance of the NOT, or longer if required by NDEP.

IV.B.4 Availability of Reports

III.B.4.a Except for data determined to be confidential under NRS 445A.665, all reports prepared in accordance with the terms of this permit that have been submitted to NDEP shall be available for public inspection at NDEP's office. Knowingly making any false statement on any such report may result in the imposition of criminal penalties as provided for in NRS 445A.710.

IV.B.5 Continuation of Coverage

- IV.B.5.a In accordance with NAC 445A.241, this permit shall remain in effect until reissued, and existing permittees shall be included in the reissued permit if a new NOI is submitted prior to the expiration date of this permit. A filing fee is not required for this submittal.

IV.B.6 Transfer of Ownership or Control

- IV.B.6.a If control or ownership of the Industrial Facility changes, the Permittee shall notify the succeeding owner or controller of the existence of this permit by letter, a copy of which shall be forwarded to NDEP. To transfer permit coverage, the new owner or operator and the previous owner shall submit a written request to NDEP in accordance with Section I.A.5.d.(i).(c). All transfer of permits shall be approved by NDEP.

IV.B.7 Annual Fee

- IV.B.7.a The Permittee shall remit an annual fee in accordance with NAC 445A.268 on or before July 1 every year.

IV.B.8 Right of Entry

- IV.B.8.a The permittee shall allow representatives of NDEP upon the presentation of credentials:
- IV.B.8.a.(i) To enter upon the industrial facility site or the permittee's premises where any records are kept under the terms and conditions of this permit; and
- IV.B.8.a.(ii) At reasonable times, to have access to and copy any records kept under the terms and conditions of this permit; to inspect any monitoring equipment or monitoring method used pursuant to this permit; perform activities required to collect information in conducting compliance investigations; and to perform any necessary sampling to determine compliance with this permit or to sample any discharge.

IV.B.9 Penalty for Violation of Permit Conditions

- IV.B.9.a NRS 445A.675 provides that any person who violates a permit condition is subject to administrative and judicial sanctions as outlined in NRS 445A.690 through 445A.705.

IV.B.10 Furnishing False Information and Tampering with Monitoring Devices

IV.B.10.a Any person who knowingly makes any false statement, representation, or certification in any application, record, report, plan or other document filed or required to be maintained by the provisions of NRS 445A.300 to 445A.730, inclusive, or by any permit, rule, regulation or order issued pursuant thereto, or who falsifies, tampers with or knowingly renders inaccurate any monitoring device or method required to be maintained under the provisions of NRS 445A.300 to 445A.730, inclusive, or by any permit, rule, regulation or order issued pursuant thereto, is guilty of a gross misdemeanor and shall be punished by a fine of not more than \$25,000 per day per violation or by imprisonment. This penalty is in addition to any other penalties, civil or criminal, provided pursuant to NRS 445A.300 to 445A.730, inclusive.

IV.B.11 Permit Modification, Suspension or Revocation

IV.B.11.a After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to, the following:

IV.B.11.a.(i) Violation of any terms or conditions of this permit

IV.B.11.a.(ii) Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts, or

IV.B.11.a.(iii) A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.

IV.B.12 Liability

IV.B.14.a Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the Permittee from any responsibilities, liabilities, or penalties established pursuant to any applicable Federal, State or local laws, regulations, or ordinances.

IV.B.13 Property Rights

IV.B.14.a The issuance of this permit does not convey any property rights, in either real or personal property, or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor any infringement of Federal, State or local laws or regulations.

IV.B.14 Severability

- IV.B.14.a The provisions of this permit are severable, and if any provision of this permit, or the application of any provisions of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

Appendix A. Definitions Used in This General Permit

Best Management Practices ("BMPs") - schedules of activities, practices (and prohibitions of practices), structures, vegetation, maintenance procedures, and other management practices to prevent or reduce the discharge of pollutants to waters of the United States. BMPs also include treatment requirements, operating procedures, and practices to control plant site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage.

Clean Water Act ("CWA") (formerly referred to as the Federal Water Pollution Control Act or Federal Water Pollution Control Act Amendments of 1972) Public Law 92-500, as amended by Public Law 95-217, Public Law 95-576, Public Law 96-483 and Public Law 97-117, 33 U.S.C. 1251 et seq. CWA and regulations means the Clean Water Act (CWA) and applicable regulations promulgated thereunder. In the case of an approved State program, it includes State program requirements.

Control Measure - refers to any BMP or other method (including effluent limitations) used to prevent or reduce the discharge of pollutants to waters of the United States.

Division – Nevada Division of Environmental Protection

Discharge - when used without qualification, means the "discharge of a pollutant."

Discharge of a Pollutant - any addition of any pollutant or combination of pollutants to "waters of the United States" from any "point source," or any addition of any pollutant or combination of pollutants to the waters of the "contiguous zone" or the ocean from any point source other than a vessel or other floating craft which is being used as a means of transportation. This includes additions of pollutants into waters of the United States from: surface runoff which is collected or channeled by man; discharges through pipes, sewers, or other conveyances, leading into privately-owned treatment works.

Discharge-related activities - activities which cause, contribute to, or result in stormwater and allowable non-stormwater point source discharges, and measures such as the siting, construction and operation of BMPs to control, reduce, or prevent pollution in the discharges.

Facility or Activity - any NPDES "point source" or any other facility or activity (including land or appurtenances thereto) that is subject to regulation under the NPDES program.

Impaired Water – a water is impaired if it does not meet its designated use(s). For purposes of this permit 'impaired' refers to threatened and impaired waters listed on NDEP's 303(d) lists; 303(d) lists generally include only waters for which TMDLs have not yet been developed. For current 303(d) Impaired Water Body listings, please refer to <http://ndep.nv.gov.bwqp/303dlist.htm>. States will generally have associated, but separate lists of

impaired waters for which TMDLs have already been established. For a list of TMDLs approved by EPA, please refer to <http://ndep.nv.gov/bwqp/tmdl.htm>.

Industrial Activity - the 11 categories of industrial activities included in the definition of "stormwater discharges associated with industrial activity."

Industrial Stormwater - stormwater runoff associated with the definition of "stormwater discharges associated with industrial activity."

Municipal Separate Storm Sewer ("MS4") - a conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, man-made channels, or storm drains):

- i. Owned or operated by a State, city, town, borough, county, parish, district, association, or other public body (created by or pursuant to State law) having jurisdiction over disposal of sewage, industrial wastes, stormwater, or other wastes, including special districts under State law such as a sewer district, flood control district or drainage district, or similar entity, or an Indian tribe or an authorized Indian tribal organization, or a designated and approved management agency under section 208 of the CWA that discharges to waters of the United States;
- ii. Designed or used for collecting or conveying stormwater;
- iii. Which is not a combined sewer; and
- iv. Which is not part of a Publicly Owned Treatment Works ("POTW") as defined at 40 CFR 122.2.

NDEP – Nevada Division of Environmental Protection

New Discharger - as used in this permit, means an operator applying for coverage under this permit for discharges not covered previously under an NPDES general or individual permit.

New Source - any building, structure, facility, or installation from which there is or may be a "discharge of pollutants," the construction of which commenced:

- after promulgation of standards of performance under section 306 of the CWA which are applicable to such source, or
- after proposal of standards of performance in accordance with section 306 of the CWA which are applicable to such source, but only if the standards are promulgated in accordance with section 306 within 120 days of their proposal.

No exposure - all industrial materials or activities are protected by a storm-resistant shelter to prevent exposure to rain, snow, snowmelt, and/or runoff.

Owner or operator - the owner or operator of any "facility or activity" subject to regulation under the NPDES program.

Person - an individual, association, partnership, corporation, municipality, State or Federal agency, or an agent or employee thereof.

Point source - any discernible, confined, and discrete conveyance, including but not limited to any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, landfill leachate collection system, vessel, or other floating craft from which pollutants are or may be discharged. This term does not include return flows from irrigated agriculture or agricultural stormwater runoff.

Primary industrial activity - includes any activities performed on-site which are identified in the narrative descriptions of 122.26(b)(14)(i), (iv), (v), or (vii), and (ix); and activities which are identified by the facility's primary SIC code. [It is recommended that this determination be based on the value of receipts or revenues or, if such information is not available for a particular facility, the number of employees or production rate for each process may be compared. The operation that generates the most revenue or employs the most personnel is the operation in which the facility is primarily engaged.] Narrative descriptions identified above include: (i) activities subject to stormwater effluent limitations guidelines, new source performance standards, or toxic pollutant effluent standards; (iv) hazardous waste treatment storage, or disposal facilities including those that are operating under interim status or a permit under subtitle C of the Resource Conservation and Recovery Act (RCRA); (v) landfills, land application sites and open dumps that receive or have received industrial wastes; (vii) steam electric power generating facilities; and (ix) sewage treatment works with a design flow of 1.0 mgd or more.

Pollutant - dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, sewage sludge, munitions, chemical wastes, biological materials, heat, wrecked or discarded equipment, rock, sand, cellar dirt, and industrial, municipal and agricultural waste discharged into water.

Qualified Personnel - Qualified personnel are those who possess the knowledge and skills to assess conditions and activities that could impact stormwater quality at your facility, and who can also evaluate the effectiveness of BMPs.

Reportable Quantity Release - a release of a hazardous substance at or above the established legal threshold that requires emergency notification. Refer to 40 CFR Parts 110, 177, and 302 for complete definitions and reportable quantities for which notification is required.

Runoff coefficient - the fraction of total rainfall that will appear at the conveyance as runoff.

Significant materials - includes, but is not limited to: raw materials; fuels; materials such as solvents, detergents, and plastic pellets; finished materials such as metallic products; raw materials used in food processing or production; hazardous substances designated under section 101(14) of CERCLA; any chemical the facility is required to report pursuant to section 313 of Title III of SARA; fertilizers; pesticides; and waste products such as ashes, slag and sludge that have the potential to be released with stormwater discharges.

Special Aquatic Sites - sites identified in 40 CFR 230 Subpart E. These are geographic areas, large or small, possessing special ecological characteristics of productivity, habitat, wildlife protection, or other important and easily disrupted ecological values. These areas are generally recognized as significantly influencing or positively contributing to the general overall environmental health or vitality of the entire ecosystem of a region.

Stormwater - stormwater runoff, snow melt runoff, and surface runoff and drainage.

Stormwater Discharges Associated with Construction Activity - a discharge of pollutants in stormwater runoff from areas where soil disturbing activities (e.g., clearing, grading, or excavation), construction materials, or equipment storage or maintenance (e.g., fill piles, borrow areas, concrete truck washout, fueling), or other industrial stormwater directly related to the construction process (e.g., concrete or asphalt batch plants) are located. (See 40 CFR 122.26(b)(14)(x) and 40 CFR 122.26(b)(15) for the two regulatory definitions on regulated stormwater associated with construction sites.)

Stormwater Discharges Associated with Industrial Activity - the discharge from any conveyance that is used for collecting and conveying stormwater and that is directly related to manufacturing, processing or raw materials storage areas at an industrial plant. The term does not include discharges from facilities or activities excluded from the NPDES program under Part 122. For the categories of industries identified in this section, the term includes, but is not limited to, stormwater discharges from industrial plant yards; immediate access roads and rail lines used or traveled by carriers of raw materials, manufactured products, waste material, or by-products used or created by the facility; material handling sites; refuse sites; sites used for the application or disposal of process waste waters (as defined at part 401 of this chapter); sites used for the storage and maintenance of material handling equipment; sites used for residual treatment, storage, or disposal; shipping and receiving areas; manufacturing buildings; storage areas (including tank farms) for raw materials, and intermediate and final products; and areas where industrial activity has taken place in the past and significant materials remain and are exposed to stormwater. For the purposes of this paragraph, material handling activities include storage, loading and unloading, transportation, or conveyance of any raw material, intermediate product, final product, by-product or waste product. The term excludes areas located on plant lands separate from the plant's industrial activities, such as office buildings and accompanying parking lots as long as the drainage from the excluded areas is not mixed with stormwater drained from the above described areas. Industrial facilities include those that are federally, State, or

municipally owned or operated that meet the description of the facilities designated under the provisions of 40 CFR 122.26(a)(1)(v).

Total Maximum Daily Loads (TMDLs) - A TMDL is the sum of the allowable loads of a single pollutant from all contributing point and nonpoint sources. It is a calculation of the maximum amount of a pollutant that a waterbody can receive and still meet water quality standards, and an allocation of that amount to the pollutant's sources. A TMDL stipulates wasteload allocations (WLAs) for point source discharges, load allocations (LAs) for nonpoint sources, and a margin of safety (MOS).

Waters of the United States - means:

- All waters which are currently used, were used in the past, or may be susceptible to use in interstate or foreign commerce, including all waters that are subject to the ebb and flow of the tide;
- All interstate waters, including interstate "wetlands";
- All other waters, such as interstate lakes, rivers, streams (including intermittent streams), mudflats, sandflats, wetlands, sloughs, prairie potholes, wet meadows, playa lakes, or natural ponds, the use, degradation, or destruction of which would affect or could affect interstate or foreign commerce, including any such waters
 - a. Which are or could be used by interstate or foreign travelers for recreational or other purposes;
 - b. From which fish or shellfish are or could be taken and sold in interstate or foreign commerce; or
 - c. Which are or could be used for industrial purposes by industries in interstate commerce;
- All impoundments of waters otherwise defined as waters of the United States under this definition;
- Tributaries of waters identified in paragraphs (1) through (4) of this definition;
- The territorial sea; and
- Wetlands adjacent to waters (other than waters that are themselves wetlands) identified in paragraphs 1 through 6 of this definition.

Waste treatment systems, including treatment ponds or lagoons designed to meet the requirements of the CWA (other than cooling ponds for steam electric generation stations as specified in 40 CFR 423) which also meet the criteria of this definition, are not waters of the United States. Waters of the United States do not include prior converted cropland. Notwithstanding the determination of an area's status as prior converted cropland by any other Federal agency, for the purposes of the CWA, the final authority regarding CWA jurisdiction remains with EPA.

Water Quality Impaired – See "Impaired Water."

NEVADA DIVISION OF ENVIRONMENTAL PROTECTION
BUREAU OF WATER POLLUTION CONTROL
901 SOUTH STEWART STREET, SUITE 4001
CARSON CITY, NV 89701-5249
PHONE: (775) 687-9418

ANNUAL INVOICE

05/02/2009

TO: Ms. Sydney Nitschke
CLARK COUNTY DEPT OF AVIATION
PO BOX 11005
Las Vegas NV 89111

INVOICE: GENERAL PERMIT ANNUAL FEE FOR FISCAL YEAR 2010

FOR: OVERTON AIRPORT - PERKINS FIELD

Industrial Stormwater General Permit

Site ID/Invoice Number: ISW- 1234

Annual Fee Due: July 1, 2009

Total Amount Due: \$200

Taxpayer ID (TIN):

In accordance with NRS 353.1467, payments to the State for \$10,000 or more must be paid electronically beginning July 1, 2008. Governmental entities are exempt. To enable electronic fee payments, starting on July 1, 2008, NDEP will accept E-check payments of any amount through our secure website <http://www.ndep.nv.gov/epayments>.

If paying by paper check please return this invoice with your payment and make checks payable to "NDEP-BWPC". Please write your Site ID/Invoice Number on the check and remit payment to the address above.

As a reminder, please note that Nevada Administrative Code (NAC) 445A.268 Section (5)(b) reads, in part, that a Permittee (discharger) who is covered under a general permit shall pay to the Director a nonrefundable fee of \$200 not later than July 1 of each year that the discharger is covered under that permit.

To Terminate coverage of the Nevada NPDES General Permit for Stormwater Discharges, the Permittee must submit a Notice of Termination ("NOT") form when their facilities no longer have any stormwater discharges associated with Industrial activity as defined in the Nevada's General Stormwater Permit or EPA regulations at 40 CFR 122.26, or when they are no longer the operator of the site.

Forms are available at: <http://ndep.nv.gov/bwpc/indnot.pdf>

If you have general questions about fees please call Stormwater Assistance at (775) 687-9430.

Additional information is available at: <http://ndep.nv.gov/bwpc/storm01.htm>

PLEASE RETURN THIS STUB WITH PAYMENT

Bureau of Water Pollution Control

Annual Fee Payment for Fiscal Year 2010

Site Name: OVERTON AIRPORT - PERKINS FIELD

Site ID/Invoice Number: ISW- 1234

Taxpayer ID (TIN):

Amount Due: \$200

New Billing Address or Contact Person:

Organization:

Contact Name:

Address:

City/State/Zip:

Phone:

Appendix B


Site Map

WO#: C:\MY DWGS\2009-YR\B-DWGS\OVT\B-253.dwg Jun 17, 2009 - 8:57am


LEGEND

- SEWER/STORMWATER FACILITIES
- PAVED SURFACE AREA
= 24.70 ACRES
- BUILDING AREA
= 0.07 ACRES
- LANDSCAPE AREA
= 0.0 ACRES
- DIRT AREA
= 247.40 ACRES


NOTE: TOTAL SITE AREA IS THE ADDITION OF THE PAVED AREA, THE BUILDING AREA, THE LANDSCAPE AREA = 273.49 ACRES. APPROX.



1" = 500'




LOCATION MAP



SCALE HORIZ. 1"=500' VERT. NONE		DATE 4/09	
PROJ. NO. NONE		DRAWING NO. B-253	
SHT. 2 OF 2		DESCRIPTION AIRPORT ENTRANCE ROAD	
DESIGNED BY DIR		DRAWN BY DIR	
DEPT. OF AVIATION • CLARK COUNTY, NV.		CHECKED BY APPROVED BY AIRPORT ENGINEER	
McCarran International Airport		OVERTON AIRPORT SWPPP SITE MAP	
LAS VEGAS • McCARRAN		INTERNATIONAL • AIRPORT	

Appendix C Drainage Map



LOCATION MAP

[illegible]

Appendix D

SWPPP Amendment Log

[illegible]

Appendix E

Inspection Records and Checklists

DEPARTMENT OF AVIATION

QUARTERLY ENVIRONMENTAL INSPECTION CHECK LIST

LOCATION: _____ AREA: _____

INSPECTED BY: _____ DATE: _____ TIME: _____

Check the appropriate box. S=SATISFACTORY U=UNSATISFACTORY NA=NOT APPLICABLE

For each UNSATISFACTORY provide a comment, corrective action taken or needed, and correction date in the last section. When you first enter an area to conduct the inspection, observe what employees are doing. Observe their behaviors first, then check conditions.

INSPECTION ITEMS/AREA (Wastes)	S	U	NA
1. Is the hazardous waste properly stored and labeled?			
2. Have the required weekly inspections been conducted?			
3. Is the universal waste properly stored and labeled?			
4. Are used rags properly stored and disposed of?			
5. Is the facility properly draining oil cans/filters properly?			
6. Are used oil containers properly stored and labeled?			
7. Are parts washer solvents properly stored and labeled?			
8. Are there any drains located near waste storage areas?			
9. Are waste fluids being promptly transferred from equipment/drip pans to waste area?			
10. Does the facility participate in recycling?			
INSPECTION ITEMS/AREA (Containers)	S	U	NA
11. Are chemical and oil containers properly stored and labeled?			
12. Are drums containing liquids stored on spill pallets?			
13. Are the spill pallets free of liquids?			
14. Are containers in good condition with no evidence of release or spillage?			
15. Are containers sealed and closed when not in use?			
16. Are tanks properly labeled?			
17. Are tanks and associated piping free of leaks/spills?			
18. Are materials stored outside properly protected?			
19. Are materials stored away from drains?			
INSPECTION ITEMS/AREA (Maintenance)	S	U	NA
20. Are drip pans or other devices utilized beneath equipment?			
21. Are painting operations limited to "touch-up" only?			
22. Does the facility have a permitted paint booth?			
23. Are spill kits present during maintenance activities and/or readily available?			
24. Are equipment and vehicles washed anywhere other than washracks?			
25. Is aircraft washing conducted properly (approved soaps, water collection, etc.)?			
26. Is there any indications of spillage or releases from any waste containers?			
27. Are protective measures in place for fueling to prevent spillage?			
28. Are excess deicing fluids being promptly cleaned up?			
29. Are the floors in maintenance areas clean and free of fluids?			
30. Does the facility have measures to prevent discharges into drains?			
31. Are vehicles and equipment checked regularly for leaks?			
32. Are leaks promptly repaired?			
33. Are batteries stored on pallets or off the ground?			
34. Are all fluids drained from inoperable or severely damaged equipment/vehicles?			
35. Is storage and parking areas kept clean and free of wind blown debris?			
36. Does the facility utilize good housekeeping measures?			
INSPECTION ITEMS/AREA (Documentation)	S	U	NA
37. Are weekly waste and container inspections documented?			
38. Does the facility have a Storm Water Pollution Prevention Plan?			
39. Does the facility have a Spill Prevention, Controls, and Countermeasure Plan?			

Annual Stormwater Inspection Report

General Information			
Tenant / Facility Name:			
Location:			
Tenant Physical Address:			
Mailing Address:			
Contact #1:		Phone Number:	
Contact #2:		Phone Number:	
24 hr Emergency Contact #:	DOA Control Center 261-5125	Fax Number:	
Date of Inspection:		Start/End Time:	
Inspector's Name(s):			
Inspector's Title(s):			
Type of Inspection:	<input type="checkbox"/> Annual <input type="checkbox"/> Other		
Facility Information			
Describe type/category of facility:			
Check all activities that apply to the facilities operations:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 50%;"><input type="checkbox"/> Aircraft Servicing</div> <div style="width: 50%;"><input type="checkbox"/> Facility Maintenance</div> <div style="width: 50%;"><input type="checkbox"/> Vehicle/Equip Storage</div> <div style="width: 50%;"><input type="checkbox"/> Aircraft Maintenance</div> <div style="width: 50%;"><input type="checkbox"/> Refuse Area</div> <div style="width: 50%;"><input type="checkbox"/> Vehicle/Equip Washing</div> <div style="width: 50%;"><input type="checkbox"/> Aircraft Washing</div> <div style="width: 50%;"><input type="checkbox"/> Vehicle/Equip Fueling</div> <div style="width: 50%;"><input type="checkbox"/> Other (please specify)</div> <div style="width: 50%;"><input type="checkbox"/> Cargo/Material Handling</div> <div style="width: 50%;"><input type="checkbox"/> Vehicle/Equip Maintenance</div> </div>		
Additional information:			

	BMP/activity	Implemented?	Maintenance Required?	Corrective Action Needed and Notes
1	Non-stormwater discharge(s): Are any non-stormwater or illicit discharges present?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
2	Sediment and Erosion Control: Are discharge points and receiving waters free of any sediment deposits?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
3	Are storm drain inlets properly protected?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
4	Are non-stormwater discharges (e.g., wash water, dewatering) properly controlled?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
5	Fueling: Is there an adequate spill kit?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
6	Maintenance: Are maintenance areas free of spills, leaks, or any other deleterious material?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
7	Spill Prevention and Response: Are spill kits readily available and easy to get to by all personnel?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
8	Facility Maintenance: Are paved areas being properly maintained and cleaned?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
9	Are containers closed and labeled?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
10	Are batteries properly stored?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
11	Are areas free from leaks from vehicles and equipment?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
12	Are good housekeeping practices being followed?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
13	Material Handling & Storage: Are chemicals and products being properly stored?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
14	Garbage handling & disposal: Is trash/litter from work areas collected and placed in covered dumpsters?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
15	Stormwater Pollution Prevention Education (training): Are employees provided annual SWPPP training? Are signs posted in appropriate areas for additional training measures (i.e. posters, stickers, etc.)?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Yes <input type="checkbox"/> No	
16	(Other)	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

POTENTIAL POLLUTANT	Potential Stormwater Exposure	Indoors	Outdoors	Comments
Anti-Freeze				
Waste Anti-Freeze				
Batteries				
Used/Waste Batteries				
Fuel				
Waste Fuel				
Herbicides				
Waste Herbicides				
Oil & Grease				
Waste Oil & Grease				
Paint				
Waste Paint				
Pesticides				
Waste Pesticides				
Soap/Cleaning Fluid				
Waste Soap/Cleaning Fluid				
Solvents				
Waste Solvents				
Other				

Non-Compliance

Describe any incidents of non-compliance not described above:

CERTIFICATION STATEMENT

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Print name and title: _____

Signature: _____ **Date:** _____

Appendix F
Non-Stormwater Discharge Assessment and Certification Sheet

**NON-STORM WATER DISCHARGE
ASSESSMENT AND CERTIFICATION**

Completed By: _____
 Title: _____
 Date: _____

Date of Test or Evaluation	Outfall Directly Observed During the Test (identify as indicated on the site map)	Method Used to Test or Evaluate Discharge	Describe Results from Test for the Presence of Non-Storm Water Discharge	Identify Potential Significant Sources	Name of Person Who Conducted the Test or Evaluation

CERTIFICATION

I, _____ (responsible corporate official), certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

A. Name & Official Title (type or print)

B. Area Code & Telephone No.

C. Signature

D. Date Signed

Appendix G

Annual Tenant Questionnaires

Stormwater Annual Questionnaire

General Information			
Tenant / Facility Name:			
Location:			
Tenant Physical Address:			
Mailing Address:			
Contact #1:		Phone Number:	
Contact #2:		Phone Number:	
List of activities conducted at this facility:			

Tenant / Facility Name:	Date Completed:
--------------------------------	------------------------

Applicable Industrial Activity	Applicable	Potential SW Exposure	Indoors	Outdoors	Contracted	Oper BMPs	Struc BMPs	Treat BMPs	Issues/Comments
Non-storm water discharges(s)									ID non-stormwater discharges
Aircraft/vehicle/equipment maintenance									ID if aircraft or vehicle or equipment
Aircraft/vehicle/equipment cleaning (washing)									ID if aircraft or vehicle or equipment
Aircraft/vehicle/equipment storage									ID if aircraft or vehicle or equipment
Vehicle & equipment painting									Most outside, Identify if have paint booth
Outdoor handling, storage, and disposal of waste & materials									
Loading/Unloading									ID if covered or not covered
Garbage handling & disposal									ID if have compactors, covered containers

➤ If available, please include photos to help identify any activity referenced above.

Tenant / Facility Name:	Date Completed:
--------------------------------	------------------------

Applicable Industrial Activity	Applicable	Potential SW Exposure	Indoors	Outdoors	Contracted	Oper BMPs	Struc BMPs	Treat BMPs	Issues/Comments
Fuel storage and delivery									
Building & grounds maintenance									
Aircraft de-icing or anti-icing									
Aircraft lavatory waste servicing									
Potable water system flushing									
Roadway/ramp/runway maintenance and cleaning									ID if sweep, snow removal, paint removal, maintenance (cold patch)
Fire suppression/fire fighting foam discharge									ID if have chemical fire suppression
Animal handling									

➤ If available, please include photos to help identify any activity referenced above.

Tenant / Facility Name:	Date Completed:
--------------------------------	------------------------

List any chemicals stored at the facility that are over 20 gallons.

Chemical Type/Name	Quantity
<hr/>	<hr/>
<hr/>	<hr/>
<hr/>	<hr/>
<hr/>	<hr/>

Hazardous Waste Generator? ☐ Yes ☐ No
 Generator Status ☐ LQG ☐ SQG ☐ CESQG
 Hazardous/Dangerous Waste ID #? ☐ Yes ☐ No _____ ID
 SARA Title III/Toxic Release Inventory (TRI)? ☐ Yes ☐ No
 PSCAA Permit? ☐ Yes ☐ No
 SPCC? ☐ Yes ☐ No
 ASTs? ☐ Yes ☐ No
 Compressed Gas Storage? ☐ Yes ☐ No
 Other:

Tenant / Facility Name:	Date Completed:
--------------------------------	------------------------

Facility-Wide BMPs	Applicable	Oper BMPs	Struc BMPs	Treat BMPs	Issues/Comments
Material Handling					
Good Housekeeping Practices					
Regular Inspections					
Preventative Maintenance					
Sediment and Erosion Control					
Management of Runoff					
Spill Prevention and Response					
Recordkeeping and Reporting					
Stormwater Pollution Prevention Education					

CERTIFICATION STATEMENT

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Print name and title: _____

Signature: _____ **Date:** _____

Appendix H

Annual SWPPP Compliance Report